



**NOTES:**

1. ALL DIMENSIONS ARE IN MILLIMETRES.
2. PANELS TO BE STEEL CONSTRUCTION. FINISH TO BE HOT DIP GALVANISED TO BS EN 1461 UNLESS SPECIFIED OTHERWISE.
3. INFILL TO BE VERTICAL BARS (NUMBER OF INFILL BARS TO BE DETERMINED BY THE MANUFACTURER).
4. FRAME TO BE HOT ROLLED STEEL HOLLOW SECTION.
5. LENGTH OF END PANEL TO BE AS SPECIFIED.
6. ALL SAFETY MEASURES ARE TO BE TAKEN WITH REGARD TO BREAKING OUT AND MECHANICAL MEANS ARE TO BE USED WHERE POSSIBLE. IF BREAKING-OUT GUNS ARE USED, THE USE OF ANTI-VIBRATION GLOVES AND ROTATION OF LABOUR IS RECOMMENDED.



Mike Jackson  
 Director of Environment, Transport  
 and Development  
 Norfolk County Council  
 County Hall  
 Martineau Lane  
 Norwich NR1 2SG

**DRAWING TITLE**

PEDESTRIAN GUARDRAIL  
 STANDARD PEDESTRIAN GUARDRAIL  
 (END PANEL)

REV.	DESCRIPTION	CHECKED	DATE

INIT.	DATE	PROJECT TITLE	
		STANDARD CONSTRUCTION DETAILS	
		SCALE	DATE
		N.T.S	May 2012
		DRAWING No.	
		NCD 400-02	